DYKSTRA EXCAVATING
3677 – 3 Mile Road NW, Grand Rapids, MI 49534
Phone: (616) 453-4827 Fax: (616) 453-5335
Email: office@jackdykstra.com

43 NORTH PH 2

PROPOSAL

January 18, 2021

IMPROVEMENTS	QUANTITY	UNIT	UNIT PRICE	AMOUNT
1. Clear & Grub	9	A.C.	4,650.00	41,850.00
2. Remove New Vegitation	9	A.C.	500.00	4,500.00
3. Topsoil Strip	8,246	C.Y.	3.25	26,799.50
4. Excavation Cut	16,321	C.Y.	3.25	53,043.25
5. Misc Machine Control	1	LS	1,500.00	1,500.00
6. Excavation Fill	15,413	C.Y.	0.30	4,623.90
7. Topsoil Respread	8,246	C.Y.	3.00	24,738.00
8. Till Seed	9	A.C.	980.00	8,820.00
9. SESC Inspections	40	Each	100.00	4,000.00
10. Silt Sacks	7	Each	180.00	1,260.00
11. Silt Fence	2,020	L.F.	2.30	4,646.00
12. Sweep & Clean Vac	1	L.S.	800.00	800.00
13. 12" Sand Subbase CL2	1,826	CY	15.30	27,937.80
14. 6" Aggregate Base	5,478	S.Y.	6.70	36,702.60
15. Asphalt Base 2" 3C & Top 1.5" 13A	1	LS	82,947.00	82,947.00
16. General Conditions	1	LS	2,800.00	2,800.00
17. Mobilization	1	LS	5,000.00	5,000.00
18. NAG S-150 Straw Matt	9,700	S.Y	1.55	15,035.00
19. NAG SC-250 Erosion Matt Spillway	50	S.Y	12.20	610.00

Sub-Total for Improvement Items	**$**	**347,613.05**

STORM SEWER ITEMS	QUANTITY	UNIT	UNIT PRICE	AMOUNT
1. 36" ADS N-12 Storm	423	L.F.	62.00	26,226.00
2. 18" ADS N-12 Storm	547	L.F.	34.50	18,871.50
3. 12" ADS N-12 Storm	472	L.F.	24.60	11,611.20
4. 36" Concrete Flared End Section	2	Each	1,455.00	2,910.00
5. 36" Bar Screen	2	Each	720.00	1,440.00
6. 18" Concrete Flared End Section	4	Each	610.00	2,440.00
7. 18" Bar Screen	4	Each	240.00	960.00
8. 12" Concrete Flared End Section	1	Each	520.00	520.00
9. 4' Dia Manhole w/ EJ 1060B Casting	5	Each	2,285.00	11,425.00
10. 5' Dia Manhole w/ EJ 1060B Casting	2	Each	3,975.00	7,950.00
11. 4' Dia Catch Basin w/ EJ 7030 Casting	5	Each	2,410.00	12,050.00
12. 5' Dia Catch Basin w/ EJ 7030 Casting	2	Each	3,180.00	6,360.00
13. Rip Rap	28	S.Y.	68.15	1,908.20
14. Stone Check Dam	2	Each	515.00	1,030.00
15. Detention Basin #2 Outlet Modificatior	1	LS	840.00	840.00
Sub-Total for Storm Sewer Items			**$**	**106,541.90**

WATERMAIN ITEMS	QUANTITY	UNIT	UNIT PRICE	AMOUNT
1. 12" Dia CL53 Watermain w/ Polywrap	1,436	L.F.	70.75	101,597.00
2. 8" Dia CL53 Watermain w/ Polywrap	273	L.F.	54.30	14,823.90
3. 12" Dia MJ Sleeve	2	Each	870.00	1,740.00
4. 12" x 8" Dia MJ Tee	1	Each	830.00	830.00
5. 12" x 6" Dia MJ Tee	3	Each	790.00	2,370.00
6. 8" x 6" Dia MJ Reducer	1	Each	300.00	300.00
7. 6" Dia 90° Bend	3	Each	290.00	870.00
8. Hydrant	4	Each	2,990.00	11,960.00
9. 6" Valve & Box	4	Each	1,065.00	4,260.00
11. 8" Valve & Box	1	Each	1,455.00	1,455.00
12. 12" Valve & Box	1	Each	2,495.00	2,495.00
12. 1" Corp, Stop & Box	18	Each	575.00	10,350.00
12. 1" Copper Water Service	1,022	L.F.	15.55	15,892.10

* Watermain includes Testing & Chlorinating
* All Sand for Utilities Onsite
* 4" Utility Crossings, 4 Tubes EA $17.55 / LF

Sub-Total for Watermain Items	**$**	**168,943.00**

GRAND TOTAL	**$**	**623,097.95**

Authorized Signer

Owner

1/25/2021

Date

JACK DYKSTRA EXCAVATING

Contractor

Signature Jack R Dykstra II - President

1-19-2021

Date