KENT COUNTY ROAD COMMISSION
1500 SCRIBNER AVE. N.W.
GRAND RAPIDS, MICHIGAN 49504
(616) 242-6910

SOIL EROSION AND SEDIMENTATION CONTROL PERMIT

Pursuant to Part 91, Soil Erosion and Sedimentation Control, of the Natural Resources and Environmental Protection Act, 1994 PA 451, as amended, approval of the Soil Erosion and Sedimentation Control Plan and **Application is hereby granted to:**

Name WOLVEN INVESTMENTS LLC - JEFF KLAASEN Permit Number: 21 \ 028

Address 1777 RW BERENDS Date Issued: 2/3/21 Open ☐

City WYOMING State MI Zip 49519 Expiration Date: 8/1/21 Closed ☐

Telephone 616-633-8317 Fax _____ E-mail Address JKLAASEN@JTBHOMES.COM

The project location is described as: 8895 HOPEWELL DR

City or Township of ALGOMA Section 35 Surface Water WETLAND/CREEK

Responsible On-Site Party DYKSTRA EXCAVATING- JACK DYKSTRA Telephone 616-456-4827 JR@JACKDYKSTRA.COM

Project Description: CONSTRUCT PRIVATE ROAD, STORM WATER MANAGEMENT - 9 ACRES

☒ **Install controls as specified on the SESC plan:** PER PLAN

☒ **Silt fence installed between earth change and surface water or wetland area.** PROPERLY TRENCHED INTO GROUND

☒ **Maintain minimum** 30 **foot vegetated buffer between earth change and surface water or wetland area.** _____

☒ **Install catch basin controls i.e. sediment bag, etc.** PROTECT ADJACENT CATCH BASINS WITH INLET PROTECTION

☒ **Establish growth on all disturbed area's by** ASAP / _____ / _____ **or within 5 days of final grading.**

☒ **Keep road clean of sediment during construction.** CONTROL TRACKING OF SOILS ONTO ROADS & SWEEP DAILY

☒ **Install mulch blankets on slopes.** 1 ON 3 SLOPES OR GREATER

☒ **Install mulch blankets or geotextile fabric on areas of concentrated flow.** _____

☒ **Other controls required:** AS REQUESTED BY INSPECTOR

☐ **Performance Deposit:** A performance deposit is required on **all** commercial projects.
The form of deposit is CHECK # 1201 **and the amount for this earth change project is $** 9,000

Permit Conditions:

1. The permitted activity shall be completed in accordance with the approved specifications, attached general and specific conditions, and approved plans dated: **1/14/21**
2. This permit does not waive the necessity for obtaining all other required federal, state, or local permits.
3. Permittee shall notify the Kent County Road Commission within **one week** after completing the permitted activity or **one week prior to the permit expiration date**, whichever comes first.

Please read General Conditions listed on the back of this permit.

PERMITTING AGENT: WAYNE HARRALL DATE 02 / 03 / 2021
INSPECTOR: BRUCE SCHUTTE

THIS PERMIT MUST BE AT PROJECT SITE AND AVAILABLE FOR INSPECTION

PERMITTEE'S COPY ☐ INSPECTOR'S COPY ☐ LOCAL GOVERNMENT DIVISION ☐ OFFICE COPY ☐